



سكاي العالمية للأعمال الفنية ذ.م.م
Sky International Technical Works LLC

West burry Tower, business bay, Dubai, UAE.
Tel:- +971 45681977
Fax: - +971 45646034
P.O BOX: - 233436

SIT-7902-PRIME-BUSBAR-052-120324 Rev.01

March 21,2024

Prime Technologies LLC
P.O Box 26736
Dubai, UAE
Tel:- +97143256555 (Extn.222)

Attention : Mr. Syed Shihabdeen
Manager

Project : Biltmore Residence, Sufouh , Dubai

Subject : Purchase Order For Electrical Busbar System.

Dear Sir,

With reference to your Quotation Ref # PT/4226/EAE/BB/06 & 06-INS dated 12/03/2024 we have the pleasure to confirm the Purchase order of supply, installation, testing and commissioning of Busbar System at Biltmore Residence, Sufouh , Dubai with final price of AED 2,500,000.00 (AED Two Million Five Hundred Thousand & Zero Fils) Excluding VAT. According to the following BOQ, terms and conditions.

For any further clarification, please do not hesitate to contact us.

Sky International Technical Works L.L.C.

For Prime Technologies LLC

Engr. Hany A. Fattah

Mr. Syed Shihabdeen

Managing Director

Tel : +971543305392
Email : hany@alalamiahuae.com

Manager

Mobile : +971552365932
Email : syedhabee@primetechnologies.ae

الصفوة للتقنية (ش.ذ.م.م)
PRIME TECHNOLOGIES (L.L.C.)
(PROJECTS & DESIGN DEPT.)
P.O. Box: 26736, Dubai - U.A.E.

Tel:- +971 45681977 , Fax: - +971 45646034 , P.O BOX: - 233436 , West Burry Tower, business bay, Dubai, UAE.



SIT-7902-PRIME-BUSBAR-052-120324 Rev.01

March 21,2024

1. Bill of Quantity

1.A For Supply, Testing & Commissioning

SNO	DESCRIPTION	QTY		U.PRICE IN AED	T.PRICE IN AED
	REFERENCE: MAILED BOQ				
	HORIZONTAL IP65 AND VERTICAL IP55				
	ALL ACCESSORIES ARE WITH WORKMANSHIP PRICES ONLY				
1	BUSBAR-01 (2500 A) FROM LV.P-01 TO LEVEL-09	88.35			
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	36	M	2,431.28	87,526.25
2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	26.25	M	2,431.28	63,821.23
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	26.1	M	2,674.41	69,802.08
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2	PCS	676.08	1,352.16
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	4	PCS	676.08	2,704.32
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1	PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1	PCS	80.58	80.58
8	KXP 2551-250 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 200A	1	PCS	1,906.10	1,906.10
9	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	8	PCS	3,176.80	25,414.38
2	BUSBAR-02 (2500 A) FROM LV.P-02 TO LEVEL-18	115.10			
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	33	M	2,431.28	80,232.40
2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	56.00	M	2,431.28	136,151.95
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	26.1	M	2,674.41	69,802.08
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2	PCS	676.08	1,352.16
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	2	PCS	676.08	1,352.16
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1	PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1	PCS	80.58	80.58
8	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	9	PCS	3,176.80	28,591.18
3	BUSBAR-03 (2500 A) FROM LV.P-03 TO LEVEL-28	156.23			
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	30	M	2,431.28	72,938.54
2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	100.13	M	2,431.28	243,444.55
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	26.1	M	2,674.41	69,802.08
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2	PCS	676.08	1,352.16
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	4	PCS	676.08	2,704.32
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1	PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1	PCS	80.58	80.58
8	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	9	PCS	3,176.80	28,591.18
4	BUSBAR-04 (2500 A) FROM LV.P-04 TO LEVEL-36	188.38			
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	36	M	2,431.28	87,526.25

Tel:- +971 45681977 , Fax:- +971 45646034 , P.O BOX: - 233436 , West Burry Tower, business bay, Dubai, UAE.



سكاي العالمية للأعمال الفنية ذ.م.م
Sky International Technical Works LLC

West burry Tower, business bay, Dubai, UAE.
Tel:- +971 45681977
Fax: - +971 45646034
P.O BOX: - 233436

SIT-7902-PRIME-BUSBAR-052-120324 Rev.01

March 21,2024

2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	129.18	M	2,431.28	314,073.37
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	23.2	M	2,674.41	62,046.29
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2	PCS	676.08	1,352.16
SNO	DESCRIPTION	QTY		U.PRICE IN AED	T.PRICE IN AED
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	4	PCS	676.08	2,704.32
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1	PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1	PCS	80.58	80.58
8	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	8	PCS	3,176.80	25,414.38
5	BUSBAR-05 (2500 A) FROM LV P-05 TO LEVEL-44	219.81			
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	39	M	2,431.28	94,820.11
2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	154.71	M	2,431.28	376,144.07
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	26.1	M	2,674.41	69,802.08
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2	PCS	676.08	1,352.16
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	3	PCS	676.08	2,028.24
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1	PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1	PCS	80.58	80.58
8	KXP 1651-160 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 125A	1	PCS	1,349.45	1,349.45
9	KXP 2551-250 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 200A	7	PCS	1,906.10	13,342.73
10	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	2	PCS	3,176.80	6,353.60
11	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 400A	1	PCS	3,176.80	3,176.80
6	BUSBAR-06 (2000 A) FROM LV P-06 TO LEVEL-21	131.74			
1	KXC-II 20507-B-STD-2000 A-BOLT-ON-STANDARD LENGTH-4.5W	36	M	1,821.46	65,572.63
2	KXC-II 20507-B-X-2000 A-BOLT-ON-SPECIAL LENGTH-4.5W	87.04	M	1,821.46	158,540.05
3	KXC-II 20507-P-X-2000 A-PLUG-IN-SPECIAL LENGTH-4.5W	8.7	M	2,003.63	17,431.54
4	KXC-II 20507-B-R-2000 A-BOLT-ON-RIGHT ELBOW-4.5W	2	PCS	450.71	901.41
5	KXC-II 20507-B-D-2000 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	4	PCS	450.71	1,802.82
6	KXC-II 20507-B-P11-2000 A-BOLT-ON-PANEL CONNECTION-4.5W	1	PCS	676.08	676.08
7	KX-S-END CLOSURE-4W-4.5W-5W (6x110)-A:161	1	PCS	68.63	68.63
8	KXP 2551-250 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 200A	1	PCS	1,906.10	1,906.10
8	KXP 2551-250 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 225A	1	PCS	1,906.10	1,906.10
9	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 400A	1	PCS	3,176.80	3,176.80
10	KXP 6351-630 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 500A	2	PCS	4,828.17	9,656.34
	FIXING CLAMPS	650	SET	3.94	2,560.87
TOTAL VATABLE AMOUNT IN AED Excluding VAT					2,320,000.00

الصقوة للتقنية (ش.ذ.م.م)
PRIME TECHNOLOGIES (L.L.C.)
PROJECTS & DESIGN DEPT.
P.O. Box: 28736, Dubai - U.A.E.

Tel:- +971 45681977 , Fax:- +971 45646034 , P.O BOX: 233436 , West Burry Tower, business bay, Dubai, UAE.

Handwritten signature or mark.



SIT-7902-PRIME-BUSBAR-052-120324 Rev.01

March 21,2024

1.B For Installation

DESCRIPTION	QTY		U.PRICE	T.PRICE
BUSBAR-01 (2500 A) FROM LV.P-01 TO LEVEL-09	88.35	m	201.78	17,826.84
BUSBAR-02 (2500 A) FROM LV.P-02 TO LEVEL-18	115.10	m	201.78	23,224.32
BUSBAR-03 (2500 A) FROM LV.P-03 TO LEVEL-28	156.23	m	201.78	31,523.34
BUSBAR-04 (2500 A) FROM LV.P-04 TO LEVEL-36	188.38	m	201.78	38,010.41
BUSBAR-05 (2500 A) FROM LV.P-05 TO LEVEL-44	219.81	m	201.78	44,352.20
BUSBAR-06 (2000 A) FROM LV.P-06 TO LEVEL-21	131.74	m	190.25	25,062.90
Total amount in AED Excluding VAT				180,000.00

Final Total Amount in AED Excluding VAT				2,500,000.00
---	--	--	--	--------------

2. Payment Terms:

A Materials

- 10% CDC as advance payment of complete order to be used for copper booking. **Prime Technologies** to submit Security Cheque against the advance payment.
- 83% 90 Days PDC as balance payment of each partial order upon completion of factory test if required by consultant & receiving **Prime Technologies's** confirmation that Materials are ready for delivery to site. 90 Days PDC Cheque will be released after Materials is delivered to site and MIR Approved by Consultant.
- 7% 30 Days PDC After completion of Testing and Commissioning and approval by consultant.

- **LME correction formula:**

L1 = Price of busbar quoted based on Old LME (8350)

L2 = Price of busbar system based on New LME

LME variation factor = $((L2 - L1)/L1) \times \text{copper impact factor} + 1$

Copper impact factor = 0.75

New unit price = Current price quoted x LME variation factor

- **Note**

LME variation factor is not applicable on tap off boxes , MCCBs and workmanship prices of accessories. copper is considered only in the linear length.



B Installation

- 90% 45 Days PDC as a progress invoice against installation and Consultant approval.
- 10% 45 Days PDC After completion of Testing and Commissioning and approval by consultant.

3. Scope of work:

- **Prime Technologies** to ensure submit FAT results prior delivery of Materials at Site.
- **Prime Technologies** responsible for delivering & installs the material as per project schedule & partial delivery order on time without delay..
- Price list fixed to end of the project without any change.
- Partial delivery accepted as project schedule through partial delivery order.
- Quantity mentioned in P.O for reference and the exact quantity's according to the site requirements and drawing approval, regardless whether increase or decreased with any percentage.
- **Prime Technologies** responsible to submit detailed isometric drawings as per site conditions within two weeks from contract signature to be reviewed and approved from consultant.
- **Prime Technologies** is full responsible to installation, Testing and Commissioning for Busbar System.
- **Prime Technologies** is full responsible to install Busbar System properly and complying with standard. **Prime Technologies** to issue installation compliance certificate once installations will be completed.
- **Prime Technologies** responsible for any kind of tests in the middle of installation to make sure properly installed to avoid any redo works or damage for the materials.
- **Prime Technologies** responsible for submission of Voltage drop calculations & Type Test Certificate.
- **Prime Technologies** responsible to provide final as built drawings and shall incorporate all changes made during the manufacturing process.
- **Prime Technologies** responsible for submission of required seismic testing certificates concerning busbar & support systems complying with project specification and Consultant requirements.
- **Prime Technologies** responsible to installation of EAE bus bar system as per bill of quantities offered
- **Prime Technologies** responsible to supply of bus bar supporting system (C&L



SIT-7902-PRIME-BUSBAR-052-120324 Rev.01

March 21,2024

- Channels, necessary accessories, fixing bolt, etc..)
- **Prime Technologies** responsible for Marking of bus bar system for installation, supporting, alignment etc..
 - **Prime Technologies** responsible for Tools of Bus bar erection (Chain Block, electrical hand tools etc..)
 - **Prime Technologies** responsible for Accessories of erection for bus bar.
 - **Prime Technologies** responsible for moving and positioning of bus bar
 - **Prime Technologies** responsible for Erection of bus bar, Fixing Elbows, Flanges & other accessories.
 - **Prime Technologies** responsible for Alignment, Torque & megger test 1000 V, continuity test, etc..
 - **Prime Technologies** Responsible For the Following Testing :

- 01- Visual Inspection
- 02-Insulation Resistance Test
- 03-Continuity and Resistance Tests
- 04-Mechanical Operation Test.
- 05-Temperature Rise Test. (Reports)
- 06-Functional Testing.

Site acceptance test will be performed at site

Busbar type test certificates will be submitted along with the submittal

4. Approval and Submittal

- **Prime Technologies** responsible to cover all consultant comments in material submittal.
- **Prime Technologies** responsible to submit method of statement for installation, Testing & Commissioning.
- In the event that consultant declines to approve the materials submittals which will be submitted by **Prime Technologies** or shall delete the whole of the scope of the supply works before the commencement thereof, then in such case sky international shall have the right to terminate this agreement and in either case no rights, claims or dues whatsoever shall accrue to **Prime Technologies** there under or in law arising from such lack of approval or deletion or resulting from such termination by sky international.
- This agreement will become in force only after getting consultant's approval on **Prime Technologies** materials submittal.

5. Manufacture & Country of Origin:

- All materials of Busbar Systems should strictly follow country of origin and manufacture submittal to client /consultant as part of approval.
- Any certification or FAT required to submit to consultant should be prepared with attested videos from factory.



- Materials should be labeled by country of origin and QC tested.
- **Prime Technologies** responsible to submit the certification of copper which will use in busbar

6. Warranty & Others Certificates:

- **Prime Technologies** shall provide warranty certificate for delivered system As per project specification and consultant requirement. Warranty will be 3 Years for Busbar system starting from Testing and commissioning acceptance date. **Prime Technologies** shall provide additional warranty duration if requested by consultant .
- **Prime Technologies** shall provide performance warranty for busbar system for 10 Years starting from Testing and commissioning acceptance date.
- **Prime Technologies** shall provide a testing certificate, certificate of origin and any additional requested certificate by the consultant for the delivered material.
- **Prime Technologies** is responsible to submit stamped as built isometric drawings after completion of work at site

7. Operation and Maintenance Manuals:

- Prior to systems acceptance and commissioning, submit one copy of an operation and maintenance manual to the project manager for review & approved from consultant. This manual shall describe to the user how to operate and maintain the systems. The user of this manual is assumed to be technically competent, but unfamiliar with these specific systems. The manuals shall be bound. At acceptance testing, turn over two hard and soft copies from manual to the owner. It is expected that user training shall be based on the manuals.
- After Accepting O & M from Consultant four way responsible for 3 times orientation for facility team about how to use & regular problem for the system.

8. Spare Parts & Maintenance Services:

- **Prime Technologies** Should submit recommended spare parts list to Sky International Technical Works LLC within one week from contract signature.
- **Prime Technologies** Should Guarantee the availability of spare parts for delivered system for 20 years from handing over date

2



9. Delivery:

- **Prime Technologies** Shall be responsible for the Delivering the materials within 6-10 weeks from date of any partial delivery order to our project at **Biltmore Residence, Sufouh , Dubai**

10. Penalty for the delay of material

- In case of **Prime Technologies** delay in delivery the material acceding to partial order released as per project schedule then **Prime Technologies** should pay penalty for delay time consider by 2 % per week up to upper limit of 10 % from amount of delayed items.

11. ND (Non Disclosure): -

- Supplier is mandatory responsible about non Disclosure for terms & conditions of this agreement as well as agreed rates to any external party (Client, Consultant, Main Contractor...). Any disclosure for any information related to this agreement by supplier and in the event of a breach of this clause, the first party is entitled to apply a fine in the amount of (10%) of the total value of the contract to be deducted from the dues of the second party.
In case of termination for SIT contract with main contractor concerning this project. supplier has no right to continue the delivery of goods related to this agreement to any other party involved in this project (main contractor, client, new contractor,...). in the event of a breach of this clause by supplier, the first party is entitled to apply a fine in the amount of (10%) of the total value of the contract to be deducted from the dues of the second party or collected directly from second party if no further dues.
- SIT shall be responsible to release the amount of any partial order that will be released following Payments terms & Conditions in Clause#2.

12. Settlement of Disputes

In the event that any disputes or difference of any kind whatsoever shall arise between SIT and the supplier in connection with or arising out of this agreement, whether during the progress of the supply/ Works or after the completion thereof and whether before or after the termination, abandonment or breach of agreement, it shall be referred to the exclusive jurisdiction of Dubai Courts.

h



سكاي العالمية للأعمال الفنية ذ.م.م
Sky International Technical Works LLC

West burry Tower, business bay, Dubai, UAE.
Tel:- +971 45681977
Fax: - +971 45646034
P.O BOX: - 233436

SIT-7902-PRIME-BUSBAR-052-120324 Rev.01

March 21,2024

13. Law Governing Sub contract

The General regulations of civil, administrative, and commercial transactions in force, in addition to the general provisions of laws and regulations in force in Dubai and /or the UAE shall apply to and shall govern this Agreement.

The Parties here to have executed this agreement as on the date and year as agreed & signed here below.

For Sky International Technical Works LLC

For Prime Technologies LLC

Sign: _____

Sign: _____

Name: Engr. Hany Abdelfattah

Name: Mr. Syed Shihabdeen

Designation: Managing Director

Designation: Manager



Tel:- +971 45681977 , Fax: - +971 45646034 , P.O BOX: - 233436 , West Burry Tower, business bay, Dubai, UAE.

Prime Technologies L.L.C.

Limited Liability Company - Paid up Capital AED 3,000,000/-

DUBAI :

P.O. Box : 26736, Dubai, U.A.E.
Tel. : +971 4 325 6555
Fax : +971 4 323 4374
E-mail : prime@primetechnologies.ae

ABU DHABI :

P.O. Box : 33824, Abu Dhabi U.A.E.
Tel. : +971 2 491 3419
Fax : +971 2 491 3420
E-mail : primeadh@primetechnologies.ae



PRIME
TECHNOLOGIES

الصفوة للتقنية شركة ذات مسؤولية محدودة

شركة ذات مسؤولية محدودة - رأس المال المدفوع -/ ٣.٠٠٠.٠٠٠ درهم

دبي :

ص.ب : ٢٦٧٣٦ - دبي، ا.ع.م.
هاتف : +٩٧١ ٤ ٣٢٥ ٦٥٥٥
فاكس : +٩٧١ ٤ ٣٢٣ ٤٣٧٤
البريد الإلكتروني : prime@primetechnologies.ae

أبوظبي :

ص.ب : ٣٣٨٢٤ - أبوظبي، ا.ع.م.
هاتف : +٩٧١ ٢ ٤٩١ ٣٤١٩
فاكس : +٩٧١ ٢ ٤٩١ ٣٤٢٠
البريد الإلكتروني : primeadh@primetechnologies.ae

Ref: PT/4226/EAE/BB/06/R1

M/s. SKY INTERNATIONAL

Attn: Mr. Hani

15-Mar-24

PROJECT: SKY SPIRAL TOWER

Sub: Quotation for Bus Bar System; Make – EAE.

Dear Sir,

With reference to the discussion had with you regarding Bus Bar system for the above-mentioned project, we are pleased to provide our revised offer as below.

Price:

Total price for the supply of EAE bus bar system as per bill of quantities attached as **Annexure-I (2 pages)** is **AED 2,320,000.00/= +5% VAT**

Please note that price quoted is based on the drawings provided by you. The final price has to be based on the Isometric drawing quantities.

All accessories are with workmanship prices only.

Technical Notes:

1. EAE Bus bars are approved by DEWA certified by DEKRA (KEMA) for all type tests required in bus bar as per IEC 61439-1&6 standards.
2. Proposed system is 3P+100%N+50%PE+Housing.
3. Housing is 2.5mm extruded aluminium housing, epoxy polyester coated to RAL 7038.
4. Class B Epoxy resin insulation on all phase and neutral conductors, separated by additional Polyester film.
5. Copper conductors are tin plated at the joints.
6. Copper conductors are 99.9% electrolytic copper.
7. IP protection degree of the bus bar is IP65 for horizontal and IP55 for vertical.
8. Tap-off boxes are mounted with L&T brand current limiting type MCCBs with bottom entry for cables.
9. All other technical specifications are same as mentioned in EAE catalogue.



ISO 9001:2008 CERTIFIED COMPANY

الصفوة للتقنية (ش.م.م.)
PRIME TECHNOLOGIES (L.L.C.)
PROJECTS & DESIGN DEPT.
P.O. Box: 26736, Dubai - U.A.E.

Handwritten signature or mark.



PRIME
TECHNOLOGIES

Terms & Conditions:

1. The offer includes following:

- **Cost of material based on delivered to site basis.**
- **Technical support (Making isometric drawings). (Free of cost)**
- **Supervising during installation. (Free of cost)**
- **Testing & Commissioning. (Free of cost)**

2. Thermography test if required can be done at additional cost.

3. Our VAT Registration number: 100395021700003.
4. The price quoted is based on the current LME Copper price, ie.**USD.8350/Ton** and subject to change according to LME price variation.
5. The offer is based on the drawings provided by you. Any change in the quantities is to be calculated based on unit price.
6. Copper will be booked on your request against 10% advance and final price will be based on LME price as of that day.
7. Copper booking will take 3 - 5 working days after receiving the copper booking confirmations.
8. We have considered the delivery by sea freight only. For any air consignment, the freight charges shall be borne by you.
9. Delivery: 12 Weeks from the date of Production Clearance.
10. Payment Terms: Will be discussed and agreed.
11. Warranty: 3 years warranty from the date of system handover against any manufacturing defects only.

We believe our offer meets your requirement and expect your valuable order.

Please do not hesitate to contact us for any clarification / confirmation.

With best regards,

For Prime Technologies LLC

Riyaz Ahamed
Estimation Engineer
(055-5340069)

Syed Shihabdeen
Manager
(055-2365932)



PROJECT : SKY SPIRAL TOWER
LIST OF MATERIAL (ANNEXURE-I)

SNO	DESCRIPTION	QTY	U.PRICE IN AED	T.PRICE IN AED
	REFERENCE: MAILED BOQ			
	HORIZONTAL IP65 AND VERTICAL IP55			
	ALL ACCESSORIES ARE WITH WORKMANSHIP PRICES ONLY			
1	BUSBAR-01 (2500 A) FROM LV.P-01 TO LEVEL-09	88.35		
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	36 M	2,431.28	87,526.25
2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	26.25 M	2,431.28	63,821.23
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	26.1 M	2,674.41	69,802.08
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2 PCS	676.08	1,352.16
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	4 PCS	676.08	2,704.32
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1 PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1 PCS	80.58	80.58
8	KXP 2551-250 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 200A	1 PCS	1,906.10	1,906.10
9	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	8 PCS	3,176.80	25,414.38
2	BUSBAR-02 (2500 A) FROM LV.P-02 TO LEVEL-18	115.10		
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	33 M	2,431.28	80,232.40
2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	56.00 M	2,431.28	136,151.95
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	26.1 M	2,674.41	69,802.08
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2 PCS	676.08	1,352.16
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	2 PCS	676.08	1,352.16
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1 PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1 PCS	80.58	80.58
8	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	9 PCS	3,176.80	28,591.18
3	BUSBAR-03 (2500 A) FROM LV.P-03 TO LEVEL-28	156.23		
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	30 M	2,431.28	72,938.54
2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	100.13 M	2,431.28	243,444.55
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	26.1 M	2,674.41	69,802.08
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2 PCS	676.08	1,352.16
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	4 PCS	676.08	2,704.32
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1 PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1 PCS	80.58	80.58
8	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	9 PCS	3,176.80	28,591.18
4	BUSBAR-04 (2500 A) FROM LV.P-04 TO LEVEL-36	188.38		
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	36 M	2,431.28	87,526.25
2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	129.18 M	2,431.28	314,073.37
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	23.2 M	2,674.41	62,046.29
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2 PCS	676.08	1,352.16

h
7

SNO	DESCRIPTION	QTY	U.PRICE IN AED	T.PRICE IN AED
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	4 PCS	676.08	2,704.32
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1 PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1 PCS	80.58	80.58
8	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	8 PCS	3,176.80	25,414.38
5	BUSBAR-05 (2500 A) FROM LV.P-05 TO LEVEL-44	219.81		
1	KXC-II 28507-B-STD-2750 A-BOLT-ON-STANDARD LENGTH-4.5W	39 M	2,431.28	94,820.11
2	KXC-II 28507-B-X-2750 A-BOLT-ON-SPECIAL LENGTH-4.5W	154.71 M	2,431.28	376,144.07
3	KXC-II 28507-P-X-2750 A-PLUG-IN-SPECIAL LENGTH-4.5W	26.1 M	2,674.41	69,802.08
4	KXC-II 28507-B-R-2750 A-BOLT-ON-RIGHT ELBOW-4.5W	2 PCS	676.08	1,352.16
5	KXC-II 28507-B-D-2750 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	3 PCS	676.08	2,028.24
6	KXC-II 28507-B-P11-2750 A-BOLT-ON-PANEL CONNECTION-4.5W	1 PCS	1,014.10	1,014.10
7	KX-S-END CLOSURE-4W-4.5W-5W (6x180-2x6x70)-A:232	1 PCS	80.58	80.58
8	KXP 1651-160 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 125A	1 PCS	1,349.45	1,349.45
9	KXP 2551-250 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 200A	7 PCS	1,906.10	13,342.73
10	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 300A	2 PCS	3,176.80	6,353.60
11	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 400A	1 PCS	3,176.80	3,176.80
6	BUSBAR-06 (2000 A) FROM LV.P-06 TO LEVEL-21	131.74		
1	KXC-II 20507-B-STD-2000 A-BOLT-ON-STANDARD LENGTH-4.5W	36 M	1,821.46	65,572.63
2	KXC-II 20507-B-X-2000 A-BOLT-ON-SPECIAL LENGTH-4.5W	87.04 M	1,821.46	158,540.05
3	KXC-II 20507-P-X-2000 A-PLUG-IN-SPECIAL LENGTH-4.5W	8.7 M	2,003.63	17,431.54
4	KXC-II 20507-B-R-2000 A-BOLT-ON-RIGHT ELBOW-4.5W	2 PCS	450.71	901.41
5	KXC-II 20507-B-D-2000 A-BOLT-ON-DOWNWARDS ELBOW-4.5W	4 PCS	450.71	1,802.82
6	KXC-II 20507-B-P11-2000 A-BOLT-ON-PANEL CONNECTION-4.5W	1 PCS	676.08	676.08
7	KX-S-END CLOSURE-4W-4.5W-5W (6x110)-A:161	1 PCS	68.63	68.63
8	KXP 2551-250 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 200A	1 PCS	1,906.10	1,906.10
8	KXP 2551-250 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 225A	1 PCS	1,906.10	1,906.10
9	KXP 4051-400 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 400A	1 PCS	3,176.80	3,176.80
10	KXP 6351-630 A-PLUG-IN-TAP-OFF BOX-EMPTY-3P-SUITABLE FOR MCCB-5W-CU Equipped with L&T MCCB 3P 36kA 500A	2 PCS	4,828.17	9,656.34
	FIXING CLAMPS	650 SET	3.94	2,560.87
TOTAL VATABLE AMOUNT IN AED				2,320,000.00
VAT AMOUNT IN AED				116,000.00
GROSS AMOUNT INCLUDING VAT IN AED				2,436,000.00

Prime Technologies L.L.C.

Limited Liability Company - Paid up Capital AED 3,000,000/-

DUBAI :

P.O. Box : 26736, Dubai, U.A.E.
Tel. : +971 4 325 6555
Fax : +971 4 323 4374
E-mail : prime@primetechnologies.ae

ABU DHABI :

P.O. Box : 33824, Abu Dhabi U.A.E.
Tel. : +971 2 491 3419
Fax : +971 2 491 3420
E-mail : primeadh@primetechnologies.ae



PRIME
TECHNOLOGIES

الصفوة للتقنية شركة ذات مسؤولية محدودة

شركة ذات مسؤولية محدودة - رأس المال المدفوع -/ ٣.٠٠٠.٠٠٠ درهم

دبي :
ص.ب. : ٢٦٧٣٦ ، دبي ، ا.ع.م.
هاتف : ٤٩٧١ ٤ ٣٢٥ ٦٥٥٥
فاكس : ٤٩٧١ ٤ ٣٢٣ ٤٣٧٤
البريد الإلكتروني : prime@primetechnologies.ae

أبوظبي :
ص.ب. : ٣٣٨٢٤ ، أبو ظبي ، ا.ع.م.
هاتف : ٩٧١ ٢ ٤٩١ ٣٤١٩
فاكس : ٩٧١ ٢ ٤٩١ ٣٤٢٠
البريد الإلكتروني : primeadh@primetechnologies.ae

Ref: PT/4226/EAE/BB/06/INS/R1

Mar-24

M/s. SKY INTERNATIONAL

Attn: Mr. Hani

15-

PROJECT: SKY SPIRAL TOWER **Sub: Quotation for Bus Bar System Installation**

Dear Sir,

We thank you for your enquiry for Bus Bar system installation for the above-mentioned project and are pleased to provide our revised offer as below.

Price:

Total price for the installation of EAE bus bar system as per bill of quantities offered is

AED 180,000/= +5% VAT

DESCRIPTION	QTY	U.PRICE	T.PRICE
BUSBAR-01 (2500 A) FROM LV.P-01 TO LEVEL-09	88.35 m	201.78	17,826.84
BUSBAR-02 (2500 A) FROM LV.P-02 TO LEVEL-18	115.10 m	201.78	23,224.32
BUSBAR-03 (2500 A) FROM LV.P-03 TO LEVEL-28	156.23 m	201.78	31,523.34
BUSBAR-04 (2500 A) FROM LV.P-04 TO LEVEL-36	188.38 m	201.78	38,010.41
BUSBAR-05 (2500 A) FROM LV.P-05 TO LEVEL-44	219.81 m	201.78	44,352.20
BUSBAR-06 (2000 A) FROM LV.P-06 TO LEVEL-21	131.74 m	190.25	25,062.90
Total amount in AED			180,000.00

Our scope includes the followings.

1. Supply of bus bar supporting system (C&L Channels, necessary accessories, fixing bolt, etc)
2. Marking of bus bar system for installation, supporting, alignment etc...
3. Tools for bus bar erection (Chain block, electrical hand tools etc...)
4. Accessories for erection of bus bar.



ISO 9001:2008 CERTIFIED COMPANY

الصفوة للتقنية (ش.ذ.م.م.)
PRIME TECHNOLOGIES (L.L.C.)
PROJECTS & DESIGN DEPT.
P.O. Box: 26736, Dubai - U.A.E.

Handwritten signature/initials.



PRIME
TECHNOLOGIES

5. Moving and positioning of bus bar
6. Erection of bus bar, fixing Elbows, Flanges & other accessories
7. Alignment, Torque & megger test 1000 V, continuity test, etc...
8. Testing & commissioning.

General terms and conditions

1. Power supply provision for working on site.

Exclusion

1. Permission from building / municipality.
2. Temporary cable supply, lift arrangement for shifting materials
3. For high level areas boom lift needs to be provided by you.
4. Scaffolding for High level areas (above 3.5 meters), all civil works (Plastering, wall opening, painting etc...)

Payment terms:

20% advance. Remaining amount 30 days from the date of invoice submission on completion of works on prorata basis.

We believe our offer meets your requirement and expect your valuable order.

Please do not hesitate to contact us for any clarification / confirmation.

With best regards,

For Prime Technologies LLC

Riyaz Ahamed
Estimation Engineer
(055-5340069)

Syed Shihabdeen
Manager
(055-2365932)

الصفوة للتقنية (ش.ذ.م.)
PRIME TECHNOLOGIES (L.L.C.)
PROJECTS & DESIGN DEPT.)
P.O. Box: 26736, Dubai - U.A.E.